

Name of work-Plantation of Cricket ground peripheral area in NIT Rourkela.

SL. NO	Description of Item	Unti	Rate	Quantity	Amount
1	Supplying and stacking of sludge at site including royalty and carriages upto 1Km (sludge measured in stacks will be reduced by 8% for payment)	Cum		600	
2	Supplying and stacking at site dump manure from badli or other approved source including carriage upto 1Km, manure measured in stacks will be reduced by 8% for payment) screened through sieve of IS designation 20mm)	Cum		600	
3	Rough dressing of trenched ground including breaking clods	Sqm.		47000	
4	Uprooting of weeds from trenched area afer 10 to 15 days of its fiooding with water including disposal of uprooted vegetation.	Sqm.		47000	
5	Fine dressing of ground.	Sqm.		47000	
6	Spreading of sludge, dump manure or and/ or good earth in required thickness (cost of sludge & dump manure and / or good earth to be paid seprately)	Sqm.		47000	
7	Mixing of earth and sludge manure in proportion specified or directed.	Sqm.		47000	
8	Cost of Grassing with "doob" grass including microdressing, leveling, hoeing, deweeding, watering and mainitenance of the lawn for 3years with application of fertiliser and manure,pesticides etc. including supplying good earth if needed (the good earth shall be paid separately) In rows 5CM apart in either direction.(Water to be supplied by NIT and 100meter lead).	Sqm.		29000	
9	Cost of Grassing with " Calcutta doob" grass including microdressing, leveling, hoeing, deweeding, watering and mainitenance of the lawn for 3years with application of fertiliser and manure,pesticides etc. including supplying good earth if needed (the good earth shall be paid separately) In rows 5CM apart in either direction.(Water to be supplied by NIT and 100meter lead).	Sqm.		18000.00	
10	Digging holes in ordinary soil and refilling the same with excavated earth mixed with dump manure or sludge in the ratio of 2.1 by volume (2 parts stacked volume of manure after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth if any with all leads and lift (cost of manure, sludge or extra good earth if needed to be paid separately)	Each		800.00	

SL. NO	Description of Item	Unti	Rate	Quantity	Amount
	Holes 90CM dia and 90CM deep				
11	Filling of earth and sludge or dump manure in the desired proportion in trenches flooding with water and levelling (cost of supplying good earth and sludge or manure and mixing excluding)	Cum		120	
12	Clearing jungle including uprooting of rank vegetation, grass brush wood, trees and sapling of grith upto 30Cm measured at a height of 1Mtr above the ground leveland removal of robbish upto a disance and 50M outside teperiphery of the area cleared.	Sqm.		10	
13	Providing and planting tree such as ficus benjamina, and other types of tree of atleast 2M height (Gurantee of 2(two) years to be given for maintance of tree) at site with required distance as per direction of Engineer in charge. (Tree should of 2M height at time of plantation and to be supplied by Anency, cost inclusive of transportation and labour for handling)	Each		500	
				GROSS TOTAL	